

**अनुरक्षण एवं अभियांत्रिकी इकाई**  
**MAINTENANCE & ENGINEERING UNIT**  
**भाकृअनुप-भारतीय कृषि अनुसंधान संस्थान**  
**ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE**  
**नई दिल्ली-१२**  
**NEW DELHI-12.**

No. 19-20/19-20/ME Unit

Dated : 22-07-2019

**e-QUOTATION NOTICE**

Online quotation are hereby invited on behalf of the Director, IARI from the Contractors Registered with CPWD, MES, Railways, MCD, PWD or other Central/State Govt./Semi Govt. agencies. The contractor must have valid IT-PAN/VAT/TIN and GST registration number and having experience of Two similar nature of works in last three years for the work mentioned below:

S. No.	Ref. No.	Name of work & Location	Estimated cost put to bid	Earnest Money	Period of Completion	Last date & time of submission of bid, EMD, e-tender processing fee and other Document as specified in the press notice	date & time of opening of bid
1		3	4	5	6	8	9
1.	No. 19-20/19-20/ME Unit	<b>Extension of JDA room in director office at IARI Pusa, New Delhi-12.</b>	<b>Rs. 2,76,312.00</b>	<b>Rs. 6,000.00</b>	<b>Two Months</b>	<b>Upto 14:30 hours on 13.08.19</b>	<b>14.08.19 at 15:00 hours</b>

Online bids are invited by the Director, ICAR-IARI on behalf of Director, IARI for entering into Quotation for the Civil work from those firms who are dealing in line and having minimum three years' experience for such in above nature of work in Government Organization/Institutions.

**EMD of Rs. 6,000/ Rupees Six Thousand Only**) should be in the form of D.D./Pay Order/Fixed Deposit Receipt/Bank Guarantee from commercial bank drawn in favour of **Director, IARI** payable at New Delhi. The original EMD should be submitted to the Tender Inviting Authority on or before the last date and time of online bid submission. The details of D.D./Pay Order/Fixed Deposit Receipt/Bank Guarantee physically sent, should tally with the details available in the scan copy and the data enter during the online bid submission time otherwise the uploaded bid will be rejected.

The Online Tender Documents can also be view from the IARI Website [www.iari.res.in](http://www.iari.res.in). & [www.eprocure.gov.in](http://www.eprocure.gov.in). **Demand Draft/Pay Order in favour of Director IARI for Rs. 500/- (Rs. Five Hundred only)** must be submitted to the Tender Inviting Authority on or before the last date and time of online bid submission. The details of D.D./Pay Order/ physically sent, should tally with the details available in the scan copy and the data enter during the online bid submission time otherwise the uploaded bid will be rejected.

**Asstt. Admn. Officer (Works)**

## Extension of JDA room in director office at IARI Pusa, New Delhi-12.

S.No	Particular	Qty.	Unit	Rate	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.50	cum	1737.45	869
2	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	All kinds of soil.	3.50	cum	252.30	883
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	0.60	cum	5789.60	3474
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
	Cement mortar 1:4 (1 cement : 4 coarse sand)	2.00	cum	6376.25	12753
5	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III): 4 graded stone aggregate 12.5mm nominal size)	1.50	sqm	347.90	522
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
	Cement mortar 1:4 (1 cement : 4 coarse sand)	3.50	cum	7809.25	27332
7	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.				
	Cement mortar 1:3 (1 cement :3 coarse sand)	3.00	sqm	956.60	2870
8	Centering and shuttering including strutting, propping etc. and removal of form for :				
	Shelves (Cast in situ)	2.00	sqm	693.05	1386
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.				
	Thermo-Mechanically Treated bars of grade Fe-500D or more.	30.00	kg	83.50	2505

10	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	0.20	cum	9763.80	1953
11	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, +B1 laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete.				
	Size of Tile 600x600 mm	8.00	sqm	1500.55	12004
12	12 mm cement plaster of mix :				
	1:4 (1 cement: 4 coarse sand)	35.00	sqm	276.15	9665
13	15 mm cement plaster on rough side of single or half brick wall of mix:				
	1:4 (1 cement: 4 coarse sand)	35.00	sqm	318.95	11163
14	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :				
	All kinds of soil				
	Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	30.00	Rm	225.45	6764
15	Providing and fixing Polyvinyl Chloride (PVC) pipes. This includes jointing of pipes & fittings, trenching ,refilling & testing of joints complete as per direction of Engineer in Charge.				
	150 mm nominal dia Pipes	30.00	Rm	550.00	16500
16	Constructing brick masonry road gully chamber 50x45x60 cm with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm pre-cast R.C.C. horizontal grating with frame complete as per standard design :				
	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	2.00	each	5209.10	10418

17	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	50.00	sqm	94.05	4703
18	Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer-in-charge.	100.00	Sqm	176.70	17670
19	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	100.00	sqm	859.35	85935
20	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with :				
	4.0 mm thick glass panes	5.00	sqm	900.55	4503
21	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	45.00	kg	101.75	4579
22	Providing non-asbestos high impact Polypropylene reinforced cement 6 mm thick corrugated sheets (as per IS: 14871) roofing up to any pitch and fixing with polymer coated J, or L hooks, bolts and nuts 8 mm dia. G.I. plain and bitumen washers or with self drilling fastener and EPDM washers etc. complete (excluding the cost of purlins, rafters and trusses), including cutting sheets to size and shape wherever required.	11.00	sqm	600.00	6600

23	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections ( galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.				
	GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.	8.00	sqm	1504.45	12036
24	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	65.00	sqm	115.15	7485
25	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :				
	Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	65.00	sqm	142.20	9243
26	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by truck of 8.5cum capacity, including loading, transporting, unloading to approved municipal dumping ground or approved by Engineer-in-charge.	1.00	per trip	2500.00	2500
<b>TOTAL</b>		<b>276313</b>			

**Subject to be following terms & conditions:-**

1. The work shall be executed as per CPWD specifications.
2. Income Tax, work Tax & work cess as per norms shall be recovered from the bill.
3. 1% water and electrical charges will be recovered from the bill if supplied by the Department.
4. The work shall start within 7 days from the date of award and complete within 45 days failing which a penalty @ 1% per day delay will be imposed on the bill amount maximum upto 10%.
5. All the materials, laboures, T&P etc. required will be arranged by the firms itself.
7. Other item to be required at site to complete the work will be executed as per the lowest quoted rates on DSR-2018.
8. The rates shall remain valid for 90 days from the date of opening of quotations/tenders.
9. A running payment may be made of athe successful completion of work for 1/2nd or more amount of work.
10. The Director, IARI has the right to reject any or all the quotation/tenders without assigning any reason.

Percentage rate to be quoted above or below in figure on 'A' above:.....

In words:.....

I/C(W & CTO)

S.T.A.(C)

**Special Instructions to the Contractors/Bidders for the e-submission of the bids online through this e-Procurement Portal**

1. Bidder should do Online Enrolment in this Portal using the option Click Here to Enroll available in the Home Page. Then the Digital Signature enrollment has to be done with the e-token, after logging into the portal. The e-token may be obtained from one of the authorized Certifying Authorities such as eMudhraCA/GNFC/IDRBT/MtnlTrustline/SafeScript/TCS.
2. Bidder then logs into the portal giving user id / password chosen during enrolment.
3. The e-token that is registered should be used by the bidder and should not be misused by others.
4. DSC once mapped to an account cannot be remapped to any other account. It can only be Inactivated.
5. The Bidders can update well in advance, the documents such as certificates, purchase order details etc., under My Documents option and these can be selected as per tender requirements and then attached along with bid documents during bid submission. This will ensure lesser upload of bid documents.
6. After downloading / getting the tender schedules, the Bidder should go through them carefully and then submit the documents as per the tender document, otherwise, the bid will be rejected.
7. The BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant coulms, else the bidder is liable to be rejected for that tender. Bidders are allowed to enter the Bidder Name and Values only.
8. If there are any clarifications, this may be obtained online through the e-Procurement Portal, or through the contact details given in the tender document. Bidder should take into account of the corrigendum published before submitting the bids online.
9. Bidder, in advance, should prepare the bid documents to be submitted as indicated in the tender schedule and they should be in PDF/XLS/RAR/DWF formats. If there is more than one document, they can be clubbed together
10. Bidder should arrage for the EMD as specified in the tender. The original should be posted/couriered/given in person to the Tender Inviting Authority, within the bid submission date and time for the tender

11. The bidder reads the terms and conditions and accepts the same to proceed further to submit the bids.
12. The bidder has to submit the tender document(s) online well in advance before the prescribed time to avoid any delay or problem during the bid submission process.
13. There is no limit on the size of the file uploaded at the server end. However, the upload is decided on the Memory available at the Client System as well as the Network bandwidth available at the client side at that point of time. In order to reduce the file size, bidders are suggested to scan the documents in 75-100 DPI so that the clarity is maintained and also the size of file also gets reduced. This will help in quick uploading even at very low bandwidth speeds.
14. It is important to note that, the bidder has to Click on the Freeze Bid Button, to ensure that he/she completes the Bid Submission Process. Bids Which are not Frozen are considered as Incomplete/Invalid bids and are not considered for evaluation purposes.
15. In case of Offline payments, the details of the Earnest Money Deposit(EMD) document submitted physically to the Department and the scanned copies furnished at the time of bid submission online should be the same otherwise the Tender will be summarily rejected.
16. The Tender Inviting Authority (TIA) will not be held responsible for any sort of delay or the difficulties faced during the submission of bids online by the bidders due to local issues.
17. The bidder may submit the bid documents online mode only, through this portal. Offline documents will not be handled through this system.
18. At the time of freezing the bid, the e-Procurement system will give a successful bid updation message after uploading all the bid documents submitted and then a bid summary will be shown with the bid no, date & time of submission of the bid with all other relevant details. The documents submitted by the bidders will be digitally signed using the e-token of the bidder and then submitted.
19. After the bid submission, the bid summary has to be printed and kept as an acknowledgement as a token of the submission of the bid. The bid summary will act as a proof of bid submission for a tender floated and will also act as an entry point to participate in the bid opening event.
20. Successful bid submission from the system means, the bids as uploaded by the bidder is received and stored in the system. System does not certify for its correctness.
21. The bidder should see that the bid documents submitted should be free from virus and if the documents could not be opened, due to virus, during tender opening, the bid is liable to be rejected.
22. The time that is displayed from the server clock at the top of the tender Portal, will be valid for all actions of requesting bid submission, bid opening etc., in the e-Procurement portal. The Time followed in this portal is as per Indian Standard Time (IST) which is GMT+5:30. The bidders should adhere to this time during bid submission.
23. All the data being entered by the bidders would be encrypted at the client end, and the software uses PKI encryption techniques to ensure the secrecy of the data. The data entered will not be viewable by unauthorized persons during bid submission and not viewable by any one until the time of bid opening. Overall, the submitted bid documents become readable only after the tender opening by the authorized individual.
24. During transamination of bid document, the confidentiality of the bids is maintained since the data is transferred over secured Socket Layer(SSL) with 256 bit encryption technology. Data encryption of sensitive fields is also done.
25. The bidders are requested to submit the bids through online eProcurement system to the TIA well before the bid submission end date and time (as per Server System Clock).

**List of Documents to be scanned and uploaded within the period of bid submission:**

1. Demand draft / Pay order / FDR / Bank Guarantee of any Scheduled Bank against EMD and Tender Fee.
2. Receipt of EMD & Tender Fee.
3. Certificate of Registration for GST.
4. Copy of PAN.
5. Enlistment of CPWD, MES, Railways, MCD, PWD or other Central/State Govt./Semi Govt. agencies.
6. Experience of two similar nature of works in last three years.

**Note: Other conditions for composite tenders and any special condition as applicable may also be added and Press Notice may be modified suitably by NIT approving authority.**



**Executive Engineer, IARI within the Period of bid submission. (The EMD document shall only be issued from the place in which the office of receiving division office is situated.) The EMD receiving Executive Engineer shall issue a receipt of deposition of earnest money deposit to the bidder in a prescribed format (enclosed) uploaded by tender inviting EE/AE in the NIQ/NIT.**

**Prescribed format of receipt of deposition of original EMD/Tender Fee along with NIT:-**

Receipt of deposition of original EMD (Receipt No...../date.....)

1. Name of work.....
2. NIT No.....
3. Estimated Cost.....
4. Amount of Earnest money deposit.....
5. Last date of submission of bid.....
6. Agency Name .....
7. EMD No. & Date .....
8. EMD Amount & Last Date .....
9. TENDER FEE .....
10. DATE & TIME .....

**This receipt shall also be uploaded to the e-tendering website by the intending bidder upto the specified bid submission date and time.**

**CERTIFICATE TO BE SIGNED BY THE TENDERER**

**CERTIFICATE**

**It is certified that I have read and understood and will comply with all instructions contained in Terms & conditions of this tender documents. All pages submitted with this tender documents from page \_\_\_\_\_ to \_\_\_\_\_ have been filled properly and signed with seal of the firm/company.**

Signature of tenderer: - \_\_\_\_\_

Name in block letters: - \_\_\_\_\_

Name of firm: \_\_\_\_\_

Full address: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

- i) Telephone No. \_\_\_\_\_
- ii) Mobile No. \_\_\_\_\_
- iii) Fax No. \_\_\_\_\_
- iv) Email id \_\_\_\_\_
- v) Website \_\_\_\_\_

**Signature of Tenderer with office seal**