

रख-रखाव एवं अभियांत्रिकी इकाई
भारतीय कृषि अनुसंधान परिषद
भारतीय कृषि अनुसंधान संस्थान
नई दिल्ली -12.

सं. 08-12/18-19/एमईयू .

दिनांक 20-09-2018

e-निवेदा सूचः

निवेदा, भा. कृ. अनु. सं., को और स एवद्वारा अधोलोखित निवेदा : ला. नि. वी., एम. ई. एस., रेलवेज, एम. सी. डी., लान , या अन्य केंद्र / राज्य सरकार / अर्द्ध सरकारी एजेंसीया के साथ पंजीकृत पात्र / एजेंसीया व विशेषकृत एजेंसीया से मु दर निवेदा आमंत्रित को जाता है । एजेंसीया के पास : , वैट/ IT तथा GST पंजीकरण से होना आनवाय है । तथा निवेदाशत व हेतु दो विगत वर्षों में दो समान क अनुभव होना चाहय ।

क्र. सं.	कार्य का नाम	अनुमानित लाग	धरोहर रा
1.	Construction & repair of Irrigation Channel in farm area of FHT at IARI Pusa, New Delhi-12.	Rs. 900918.00	Rs. 18500.00

ई-निवेदा आतम ताथ

: 22-10-2018 को 14.30 बजे तक

ई-निवेदा खुलने व ट

: 23-10-2018 को 15.00 बजे तक

निवेदा को व

: रू. 500/- मात्र (अप्रातदय)

इच्छुक एव पात्र एज निवेदा विवरण देखने के लिए तथ ई-निवेदा प्रस्तुत करने के

<http://eprocure.gov.in>

सहायक प्रशासनिक आ

(निमोण/ एम. ई. यूनेट)

**MAINTENANCE & ENGINEERING UNIT
ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE
NEW DELHI-12.**

No. 08-12/18-19ME Unit

Dated : 20-09-2018

e-QUOTATION NOTICE

Item/percentage rate sealed Quotation are hereby invited on behalf of the Director, IARI from the Contractors Registered with CPWD, MES, Railways, MCD, PWD or other Central/State Govt./Semi Govt. agencies. The contractor must have valid IT-PAN/VAT/TIN and GST registration number and having experience of two similar nature of works in last two years for the work mentioned below :

S.N	Name of work	Estimated cost / Item Rate	Earnest Money
1.	Construction & repair of Irrigation Channel in farm area of FHT at IARI Pusa, New Delhi-12.	Rs. 900918.00	Rs. 18500.00

Last date & time submission of e-tender processing : up to 14:30 hours of 22.10.18

Opening of e-tender : 15:00 hours of 23.10.18

Tender Fee : Rs. 500/- (Non-refundable)

Desirous and eligible agencies for details & submission to e-tender may visit <http://eprocure.gov.in>

Asstt. Admn. Officer (Works)

Construction & repair of Irrigation Channel in farm area of FHT at IARI Pusa, New Delhi-12.

S.No	Item no.	Particular	Qty.	Unit	Rate	Amount
1	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	750	sqm	22.40	16800
2	2.6	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.				
	2.6.1	All kinds of soil	108.00	Cum.	125.95	13603
3	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level				
	4.1.10	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	24.00	Cum.	4209.05	101017
4	6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
	6.1.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	58.00	Cum.	4970.30	288277
5		Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.				
	11.3.1	40 mm thick with 20 mm nominal size stone aggregate	240.00	sqm	362.60	87024
6	4.2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc., up to floor five level, excluding the cost of centering, shuttering and finishing:				
	4.2.3	1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	9.50	cum	6547.70	62203
7	13.9	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement.				
	13.9.1	12 mm cement plaster	730	sqm	234.7	171331

8	13.10	15 mm cement plaster 1 : 3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall.	500.00	sqm	265.95	132975
9	M.R.	P/f of 200 mm dia PVC pipe, as per the direction of engineer-in-charge.	15.00	metre	611.30	9170
10	M.R.	P/f of 200 mm dia PVC cap over the pipe, as per the direction of engineer-in-charge.	20.00	each	234.30	4686
11		Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layersot exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	110.00	cum	125.75	13833
TOTAL			900918			

Subject to be following terms & conditions:-

1. The work shall be executed as per CPWD specifications.
2. Income Tax, work Tax & work cess as per norms shall be recovered from the bill.
3. 1% water and electrical charges will be recovered from the bill if supplied by the Department.
4. The work shall start within 7 days from the date of award and complete within three months failing which a penalty @ 1% per day delay will be imposed on the bill amount maximum upto 10%.
5. GST will be paid extra as per the norms of ministry of finance.
6. All the materials, laboures, T&P etc. required will be arranged by the firms itself.
7. The agency shall deposit security @ 5% of the sanctioned amount including EMD.
8. Any other item to be required at site to complete the work will be executed as per the lowest quoted rates on DSR-2016.
9. The rates shall remain valid for 180 days from the date of opening of quotations/tenders.
10. A running payment may be made of athe successful completion of work for 1/2nd or more amount of work.
11. The Director, IARI has the right to reject any or all the quotation/tenders without assigning any reason.

Percentage rate to be quoted above or below in figure on 'A' above:.....

In words:.....

I/C(W)

T.A.(C)