

रख-रखाव एवं अभियांत्रिकी इकाई  
भारतीय कृषि अनुसंधान परिषद  
भारतीय कृषि अनुसंधान संस्थान  
नई दिल्ली -12.

सं. KK-140/16-17/एमईयू .

दिनांक 23-10-2018

**e-निवेदा सूचना**

निवेदा, भा. कृ. अनु. सं., को और स एवद्वारा अधोलोखित निवेदा : ला. नि. वी., एम. ई. एस., रेलवेज, एम. सी. डी., लान , या अन्य केंद्र / राज्य सरकार / अर्द्ध सरकारी एजेंसीया के साथ पंजीकृत पात्र / एजेंसीया व विशेषकृत एजेंसीया से मु दर निवेदा आमंत्रित को जाता है। एजेंसीया के पास : , वैट/ 1ट तथा GST पंजीकरण से होना आवश्यक है। तथा निदेशित हेतु दो विगत वर्षों में दो समान क अनुभव होना चाहिए।

क्र. सं.	कार्य का नाम	अनुमानित लाग	धरोहर रा
1.	P/f tiles in Type-III, Quarters, in KKRC at IARI, New Delhi-12	Rs. 4,51,662.00	Rs. 10,000.00

ई-निवेदा आत्म तौर

: 23-11-2018 को 14.30 बजे तक

ई-निवेदा खुलने के लिए

: 24-11-2018 को 15.00 बजे तक

निवेदा को व

: रु. 500/- मात्र (अप्रतिदेय)

इच्छुक एवं पात्र एज

निवेदा विवरण

देखने के लिए तथ

ई-निवेदा

प्रस्तुत करने

<http://eprocure.gov.in>

सहायक प्रशासनिक आ

(निम / एम. ई. यूनट )

**MAINTENANCE & ENGINEERING UNIT  
ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE  
NEW DELHI-12.**

No. KK-140/16-17/ME Unit

Dated : 23-10-2018

**e- QUOTATION NOTICE**

Item rate sealed Quotation are hereby invited on behalf of the Director, IARI from the Contractors Registered with CPWD, MES, Railways, MCD, PWD or other Central/State Govt./Semi Govt. or Specialize agencies. The contractor must have valid IT-PAN/VAT/TIN and GST registration number and having experience of two similar nature of works in last two years for the work mentioned below :

<b>S.N</b>	<b>Name of work</b>	<b>Estimated cost / Item Rate</b>	<b>Earnest Money</b>
<b>1.</b>	<b>P/f tiles in Type-III, Quarters, in KKRC at IARI, New Delhi-12</b>	Rs. 4,51,662.00	Rs. 10,000.00

**Last date & time submission of e-tender processing** : up to 14:30 hours of 23.11.18

**Opening of e-tender** : 15:00 hours of 24.11.18

**Tender Fee** : Rs. 500/- (Non-refundable)

**Desirous and eligible agencies for details & submission to e-tender may visit** <http://eprocure.gov.in>

**Asstt. Admn. Officer (Works)**

<b>Name of work: P/f tiles in Type-III, Quarters, in KKRC at IARI, New Delhi-12</b>						
<b>S. No:</b>	<b>ITEM OF WORK</b>	<b>QTY</b>	<b>UNIT</b>	<b>RATE</b>	<b>AMOUNT</b>	<b>D.S.R-2014 Item No:</b>
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	300	Sqm	Rs. 20.05	Rs. 6015.00	15.56
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	10	cum	Rs. 892.70	Rs. 8927.00	15.2.1
3	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	300	sqm	Rs. 836.65	Rs. 250995.00	11.36
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) .	10	cum	Rs. 4,004.00	Rs. 40040.00	4.1.10
5	Providing and laying ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1 <sup>st</sup> quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Gray, Fume Red Brown, kaid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joins with white cement and matching pigment etc, complete.	100	sqm	Rs. 785.40	Rs. 78,540.00	11.37

6	Proving and fixing 18 mm thick gang saw cut mirror polished pre moulded and pre polished) machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement :P 4 coarse sand ) with joints tretated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing , curing, moulding and poishing to edge to give high gloss finish etc. complete at all levels. Raj Nagar Plain white marble/Udaipur geen marble/Zebra black marble. Area of slab over 0.50	26	cum	Rs.2,463.55	Rs.64,052.30	8.2.1.2
7	Disposal of building rubbish/ malba/similar unserviceable , dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	25	Cum	Rs. 123.70	Rs. 3,092.50	15.6
	<b>Total</b>				<b>Rs. 4,51,661.80</b>	
				<b>Say</b>	<b>Rs. 4,51,662.00</b>	

**Subject to be following terms & conditions:-**

1. The work shall be executed as per CPWD specifications.
  2. Income Tax, work Tax & work cess as per norms shall be recovered from the bill.
  3. 1% water and electrical charges will be recovered from the bill if supplied by the Department.
  4. The work shall start within Two days from the date of award and complete within Twenty days failing which a penalty @ 1% per day delay will be imposed on the bill amount maximum upto 10%.
  5. All the materials laboures, T&P etc. required will be arranged by the firms itself.
  6. The agency shall deposit security @5% of the sanctioned amount including EMD.
  7. The Director, IARI has the right to reject any or all the quotation/tenders without assigning any reason.
  8. GST will be paid extra as per the norms of ministry of finanace. Percentage rate to be quoted above or below in figure:.....
- In**
- words:.....Name with stamp & Signature of the Agency:.....

STA ( Civil)